

W.M. MILLER LLC

P.O.BOX 216

SHIPSHEWANA IN 45465

Estimate

Date	Estimate #
6/18/2026	1143

Name / Address
Howe Fire Department 175 W State Road 120 Howe IN 46746

Project				
Exterior Improveme...				
Description	Qty	U/M	Rate	Total
labor,materials and equipment to install 6" sewer and drain piping (for down spout guttering)	350	ft	22.00	7,700.00
labor, materials and equipment to install 8" schedule 40 drain piping(to carry down spout water and catch basin water to northwestern corner of property)	300	ft	31.50	9,450.00
labor ,materials and equipment to install 30" wide by 48" deep catch basin with heavy duty steel drain casting	2		1,850.00	3,700.00
labor ,materials and equipment to install 6" diameter by 7' pipe bollards (at new O.H.D.S	6	ea	475.00	2,850.00
machine time to regrade and compact lot on northside of bldg .	24	hr	195.00	4,680.00
#53 crushed asphalt millings	4	ld	798.3875	3,193.55
labor,materials and equipment to ;prep,pour and finish 7 inch exterior concrete slab reinforced with 1\2" rebar 2' on.c.both ways (30'by50' on north side of Bldg in front of O.H.D.s)	1,500	sqft	11.75	17,625.00
labor,materials and equipment to ;prep,pour and finish 4 inch exterior concrete sidewalks reinforced with 1\2" rebar 3' on.c. both ways (5' by 50' sidewalks on north side of Bldg);	250	sqft	15.00	3,750.00
Total				

Phone #	Fax #
574 320 2768	