

W.M. MILLER LLC

P.O.BOX 216
SHIPSHEWANA IN 45465

Estimate

Date	Estimate #
6/18/2026	1143

Name / Address
Howe Fire Department 175 W State Road 120 Howe IN 46746

Project				
Exterior Improveme...				
Description	Qty	U/M	Rate	Total
labor,materials and equipment to ;prep,pour and finish 5 inch exterior concrete slab reinforced with 1\2" rebar 3' on.c. both ways (96' by 10' wide,curb face sidewalks on west side of Bldg and beside O.H.D. approach also includes area on south west corner to connect sidewalks to existing concrete pavement)	1,036	sqft	13.50	13,986.00
labor,materials and equipment to ;prep,pour and finish 3' by 12' by 4 inch exterior concrete slab (for ac units on north side of bldg);	36	sqft	32.00	1,152.00
labor and equipment to grind concrete at new O.H.D.s on north side of Bldg	2	ea	550.00	1,100.00
Note;All exterior concrete includes;Grading and compaction of subgrade-Formwork-4000 psi limestone air entrained concrete-broomfinish-cure an seal- sawcut control joints				
Total			\$69,186.55	

Phone #	Fax #
574 320 2768	